



Construction Notice



August 4, 2021

New Watermain Installation from Limoges to Cheney

Contract: W/S 09-2021
Start Date: August 23, 2021
End Date: April, 2022
**Timeline is subject to change.*

The Municipality of the Nation and the City of Clarence Rockland will be constructing a new water transmission main from the elevated tower in Cheney to the water treatment plant in Limoges. This new water main will provide the village of Limoges with a more sustainable water source and provide potable water for the future growth of the community.



The majority of the construction will be performed using HDD methods, meaning that the pipe is horizontal directionally drilled below the surface and not open excavated. This greatly reduces the impact on all existing infrastructure and private property. All proposed work will be performed in municipal right of ways and not on private property. No service connections will be made along the alignment, as this water main is only a transmission water main.







Construction Notice



WORK DETAILS

The proposed watermain is Approximately 10km long, the watermain alignment is shown above. The primary method of watermain installation will be via directional drilling method combined with a series of Connection pits typically 20 feet in length 12 feet in depth. We anticipate to start the construction the week of August 23rd and we're projecting to have it complete early in the new year. During that time, resident directly affected by our construction (i.e: driveway access) will be notify with a separate notice but otherwise your services shouldn't be interrupted.






- You may experience dust, noise and other inconveniences including standby generators for dewatering pumping operations. The Municipality will make efforts to reduce the impacts. We appreciate your patience.
- Property owners located along the watermain alignment should remove items located within municipal property limits, such as landscaping and / or decorative objects.
- The Municipality will not be responsible for damage to any privately owned items on Municipal property.

	Work Hours: Work will take place from 7 a.m. to 9 p.m., Monday to Friday, with work after hours and on weekends as required.
	Pre-Construction Inspection: Prior to commencing any Contract Work the Contractor will conduct, with the Contract Administrator, a condition survey of existing buildings, bridges, culvert structures to remain, sidewalks, boulevards, curbs and gutters, trees and landscaping, line paintings, traffic signage, monitoring wells, hydro poles, wires, fencing, retaining walls, maintenance hole and chamber covers and grating, pavement, survey bench marks and monuments which may be affected by Work.
	Water Service Disruptions: If you are already on municipal water and reside along the new water main alignment no water service disruptions are anticipated during construction. Unless an <i>emergency water shut off</i> is required due to unforeseen circumstances.
	Private Surface Well and Drilled Well: If you have a surface well or a drilled well on your property, and are along the water main construction alignment you will be receiving a well survey form to fill out and return. Once completed you must contact our Environmental Consultants (Golder) to assist in monitoring your well prior to construction. Golder will be coordinating appointments to collect pre-construction water samples from private wells to establish baseline water quality. Results will be provided to residents free of charge.



Construction Notice



	<p>Road and Sidewalk Access: In order to complete the work in a safe manner, there will be road and sidewalk restrictions within the construction work zone. Access for emergency vehicles will be maintained at all times.</p> <p>Driveway Access: The contractor will notify you of any temporary restrictions to your driveway access. If your property has two entrances, one entrance will be kept open at all times.</p>
	<p>Traffic Management: Efforts have been made to manage traffic in the area for the safety of workers, road users and residents. Road users should expect delays and increased traffic on nearby main and side streets.</p> <p>Traffic on Limoges rd, Indian Creek rd, and Russell rd may be reduced to one lane at different times during construction.</p>
	<p>Parking: Parking in the active work zone is not permitted due to space requirements for construction equipment and materials. If your parked vehicle affects the construction work, it will be re-located with no charge to the owner.</p>
	<p>Garbage & Recycling: Please follow your normal routine. If required, the contractor will move bins to an appropriate location and return them. <i>Please ensure that you label your bins with your address.</i></p>
	<p>Restoration: The construction work area will be restored with sod and/or asphalt where required. Interlocking bricks, flagstone on a granular base, or other similar features that are removed from public and private property during construction will be replaced. Lawn seeding and/or laying of sod will be done as needed during ideal growing seasons only - in the spring (April to June) and fall (September to October). Permanent restoration work will take place within 12 months.</p>

If you have questions about the upcoming work, please contact us.

General Contractor (Robert Excavating)	Francis Bertrand @ (613) 443-2311 Email: Francis@robertx.ca
Contract Administrators (CIMA+)	Stephen Rocque (613) 769-4328 Email: stephen.rocque@cima.ca
The Nation Municipal Water/Wastewater Office	(613) 443-1425 Email: drenaud@nationmun.ca

Thank you for your patience. Critical infrastructure for all of us is well worth the wait.